

Telescoping Mast Guy Kits

NOW AVAILABLE

ROHN Products now offers R-618, 6 strand 18 gauge galvanized wire. R-618 guy wire is shipped in cartons of 1,000'. Each carton is made up of twenty 50' interconnected coils.

ROHN's new R-GAS4303, 3' x 1/2" Screw Anchors offer a low-cost anchor option.



Use R-61820GRPL Gripples for easy installation.



3-Way Guy Kits

R-H203WAYGUY

Actual Wire Required - 200'

H20

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 3 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 12 | R-61820GRPL | 618/620 Gripple |

R-H303WAYGUY

Actual Wire Required - 400'

H30

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 3 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 18 | R-61820GRPL | 618/620 Gripple |

R-H403WAYGUY

Actual Wire Required - 650'

H40

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 3 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 24 | R-61820GRPL | 618/620 Gripple |

R-H503WAYGUY

Actual Wire Required - 1000'

H50

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 3 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 30 | R-61820GRPL | 618/620 Gripple |

4-Way Guy Kits

R-H204WAYGUY

Actual Wire Required - 250'

H20

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 4 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 16 | R-61820GRPL | 618/620 Gripple |

R-H304WAYGUY

Actual Wire Required - 500'

H30

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 4 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 32 | R-61820GRPL | 618/620 Gripple |

R-H404WAYGUY

Actual Wire Required - 800'

H40

- | | | |
|----|-------------|-----------------------------|
| 1 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 4 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 32 | R-61820GRPL | 618/620 Gripple |

R-H504WAYGUY

Actual Wire Required - 1200'

H50

- | | | |
|----|-------------|-----------------------------|
| 2 | R-618 | 1000' - 6 Strand/18 GA Wire |
| 4 | R-GAS4303 | 3' x 1/2" Screw Anchor |
| 40 | R-61820GRPL | 618/620 Gripple |

Additional Accessories Available

Universal Ridge Mounts

R-UM20

R-UM30

R-UM40

R-UM50



Universal Ridge Mount

R-ETMB



Ground Mounts

R-GTML

